

New DDX Type F PrePaK

September 2011

Dear Valued Customer:

Reliable has expanded its PrePaK product line with the new **DDX Type F PrePaK** -

- Utilizes the **lightweight DDX deluge valve** with Type F (Electric/Pneumatic Galvanized Trim)
- Completely self-contained, supervised preaction system that can be readily installed within a floor space of less than five square feet (0.46 square meters)
- Requires **just three piping connections** - water supply, sprinkler system and drain
- 10 psi - 26 psi (0,7 bar - 1,8 bar) of system supervising air pressure
- Available with **optional** nitrogen installation kit, air compressor and tank, releasing control panel for a 120 VAC / 60Hz or a 220 VAC / 50 Hz power supply
- Sizes: 2" (50mm), 2 ½" (65mm), 3" (80mm), 4" (100mm) & 6" (150mm)
- **Two Cabinet sizes** offered -
 - 24" (0.61 m) W x 27" (0.69 m) D x 68" (1.73 m) H for **2", 2 ½" and 3" sizes**
 - 25.7" (0.65 m) W x 28.9" (0.73 m) D x 68" (1.73 m) H for **4" & 6" sizes**
- FM Approved and cULus Listed
- Designed, manufactured and tested in Reliable's Liberty, SC manufacturing facility
- For more information and a full list of custom options, please refer to **Bulletin 747**

Thank you again for choosing Reliable - your one source for all your fire protection needs.

Sincerely,



Michael R. Fee
Vice President, Marketing & Sales Operations