

# MODEL FCA FLOOR CONTROL ASSEMBLY

*Preassembled unit includes all NFPA required components for a Floor Control Assembly.*

Includes:

- Riser check valve
- Waterflow switch
- Control valve
- Test and drain valve
- Listed pressure relief valve

Factory assembled at Reliable in Liberty, SC.

Groove x Groove inlet/outlet connections and modular components that can be independently rotated – ideal for tight spaces.

Features the Reliable model TD Test and Drain Valve.

*Arrives on-site tagged\* ready for installation.*

Sizes: 2" (50 mm), 2½" (55 mm), 3" (80 mm), & 4" (100 mm).

**See Technical Bulletin 619**

**Reliable®**

[www.reliablesprinkler.com/fca](http://www.reliablesprinkler.com/fca)

\* when tagging instructions are included with your order.

